IAN BANHAM & ASSOCIATES ELECTRICAL

PROJECT : B+G+M+1 FLOOR CAR SHOWROOM & OFFICE BUILDING DETAILS OF CONNECTED LOAD/MAX. DEMAND

SMDBREF : SMDB-GE1 CONSULTANT : M/S. IAN BANHAM & ASSOCIATES LOCATION : ELECT ROOM

SR.	CIRCUIT	SP/	RATING - AMPS			FAULT	PVC/XLPE	CABLE SIZE		LENGTH	ECC	CONNECTED LOAD - KW				KWH METER			REMARKS
NO	FEEDER	TP	ACB	МССВ	MCB	DUTY	SWA/PVC/SC	2/4x1C	2/3/4C	OF	SIZE -1C	R-PHASE	Y-PHASE	B-PHASE	TOTAL	1 Ph	3 Ph	V/HV CT	
	DB NO.					KA		mm²	mm²	CABLE (Mtrs)	mm²	kW	kW	kW	kW	(1)	(2)	(4)	
	INCOMER	TP		250 (N/A)		35	FIRE PROOF		4C 150		1C 70								
	OUTGOING	GOING																	
1	DB-GE1	TP		40		35	FIRE PROOF		4C 10		1C 10	4.30	3.70	2.10	10.10				*
2	DB-GE2	TP		40		35	FIRE PROOF		4C 10		1C 10	4.00	3.40	2.60	10.00				*
3	DB-ME1	TP		40		35	FIRE PROOF		4C 10		1C 10	2.80	2.70	2.90	8.40				*
4	DB-ME2	TP		40		35	FIRE PROOF		4C 10		1C 10	2.80	3.00	3.20	9.00				*
5	DB-1E1	TP		40	GE	35	FIRE PROOF		4C 10		1C 10	4.40	3.70	4.10	12.20				*
6	DB-1E2	TP		40		35	FIRE PROOF		4C 10		1C 10	1.60	1.60	0.50	3.70				*
7	LIFT-1	TP		63		35	FIRE PROOF		4C 16		1C 16	5.00	5.00	5.00	15.00				*
8	LIFT-2	TP		63		35	FIRE PROOF		4C 16		1C 16	5.00	5.00	5.00	15.00				*
9	PANORAMIC LIFT	TP		63		35	FIRE PROOF		4C 16		1C 16	5.00	5.00	5.00	15.00				*
10	LIFT-1 CONTROL	SP		20		35	FIRE PROOF		2C 4		1C 4	0.50			0.50				*
10	LIFT-2 CONTROL	SP		20		35	FIRE PROOF		2C 4		1C 4		0.50		0.50				*
10	PANORAMIC LIFT CONTROL	SP		20		35	FIRE PROOF		2C 4		1C 4			0.50	0.50				*

CONT'D...