IPROJECT ·	B+G+M+1 FLOOR CAR SHOWROOM & OFFICE DETAILS OF CONNECTED LOAD/MAX. DEMAND

SMDB REF : SMDB - BE1 (CONT'D) CONSULTANT : M/S. IAN BANHAM & ASSOCIATES LOCATION : ELECT ROOM

00	R. CIRCUIT SP/ RATING - AMPS						FAULT PVC/XLPE CABLE SIZE LENGTH					ECC CONNECTED LOAD - KW					NAI	DEMARKO	
SR.		1		RATING - AMPS		FAULT			CABLE SIZE		ECC			KWH METER 1 Ph 3 Ph LV/HV CT			REMARKS		
NO	FEEDER	TP	ACB	МССВ	MCB		SWA/PVC/SC		2/3/4C	OF	SIZE -1C	1				1	l		
	DB NO.					KA		mm²	mm²	CABLE (Mtrs)	mm²	kW	kW	kW	kW	(1)	(2)	(4)	
	INCOMER	TP		225 (N/A)		35	FIRE PROOF		4C 120		1C 70								
	OUTGOING																		
13	SUMP PUMP	TP		20		35	XLPE/SWA/PVC		4C 4		1C 4	0.50	0.50	0.50	1.50				*
																			·
																			·
5	SMDB - BE1 CONNECTED TO MDB-E					TOTAL CONNECTED LOAD PER PHASE					36.47	35.37	35.47	107.30				TOTAL	

DEMAND FACTOR...... MAX. DEMAND.......kW TOTAL CONNECTED LOAD (3 PHASE)...107.30...kW TOTAL BUILD - UP AREA ACTUAL LOAD (3 PH)......kW

CONSULTANTS: **M/S. IAN BANHAM AND ASSOCIATES**TEL: 04 - 370 5777

FAX: 04 - 370 5888

(1 PHASE) (3 PHASE)