IAN BANHAM & ASSOCIATES ELECTRICAL

PROJECT : B+G+M+1 FLOOR CAR SHOWROOM & OFFICE BUILDING DETAILS OF CONNECTED LOAD/MAX. DEMAND

SMDB REF : SMDB - BE1 CONSULTANT : M/S. IAN BANHAM & ASSOCIATES LOCATION : ELECT ROOM

SR.	CIRCUIT	SP/	RATING - AMPS			FAULT	PVC/XLPE	CABLE SIZE		LENGTH	ECC	CONNECTED LOAD - KW			KW	KWH METER			REMARKS
NO	FEEDER	TP	ACB	МССВ	MCB	DUTY	SWA/PVC/SC	2/4x1C	2/3/4C	OF	SIZE -1C	R-PHASE	Y-PHASE	B-PHASE	TOTAL	1 Ph	3 Ph	LV/HV CT	
	DB NO.					KA		mm²	mm²	CABLE (Mtrs)	mm²	kW	kW	kW	kW	(1)	(2)	(4)	
	INCOMER	TP		225 (N/A)		35	FIRE PROOF		4C 120		1C 70								
	OUTGOING	GOING																	
1	DB-BE1	TP		40		35	FIRE PROOF		4C 10		1C 10	5.30	4.20	4.30	13.80				*
2	CPEF	TP		40		35	FIRE PROOF		4C 10		1C 10	5.33	5.33	5.33	16.00				*
3	GEF	TP		40		35	FIRE PROOF		4C 10		1C 10	5.50	5.50	5.50	16.50				*
4	GMF	TP		40		35	FIRE PROOF		4C 10		1C 10	5.50	5.50	5.50	16.50				*
5	SEWAGE LIFT STAIOION -1	TP		32		35	XLPE/SWA/PVC		4C 6		1C 6	0.50	0.50	0.50	1.50				*
6	TMF	TP		32		35	FIRE PROOF		4C 6		1C 6	2.33	2.33	2.33	7.00				*
7	TMF	TP		32		35	FIRE PROOF		4C 6		1C 6	2.33	2.33	2.33	7.00				*
8	TEF	TP		32		35	FIRE PROOF		4C 6		1C 6	2.33	2.33	2.33	7.00				*
9	TEF	TP		32		35	FIRE PROOF		4C 6		1C 6	2.33	2.33	2.33	7.00				*
10	SUMP PUMP	TP		20		35	XLPE/SWA/PVC		4C 4		1C 4	0.50	0.50	0.50	1.50				*
11	JOCKEY PUMP	TP		32		35	FIRE PROOF		4C 6		1C 6	2.17	2.17	2.17	6.50				*
12	FIRE CIRCULATION PUMP	TP		20		35	FIRE PROOF		4C 4		1C 4	1.83	1.83	1.83	5.50				*

CONT'D...