PROJECT: B+G+M+1 FLOOR CAR SHOWROOM & OFFICE BUILDING DETAILS OF CONNECTED LOAD/MAX. DEMAND

SMDB REF : SMDB - BE3 CONSULTANT : M/S. IAN BANHAM & ASSOCIATES LOCATION : ELECT ROOM

BASEMENT

| SR. | CIRCUIT                       | SP/ | RATING - AMF |              | IPS F | FAULT                          | PVC/XLPE     | CABLE SIZE |        | LENGTH       | ECC      | CONNECTED LOAD - KW |         |         |       | KWH METER |      |          | REMARKS           |
|-----|-------------------------------|-----|--------------|--------------|-------|--------------------------------|--------------|------------|--------|--------------|----------|---------------------|---------|---------|-------|-----------|------|----------|-------------------|
| NO  | FEEDER                        | TP  | ACB          | МССВ         | MCB   | DUTY                           | SWA/PVC/SC   | 2/4x1C     | 2/3/4C | OF           | SIZE -1C | R-PHASE             | Y-PHASE | B-PHASE | TOTAL | 1 Ph      | 3 Ph | LV/HV CT |                   |
|     | DB NO.                        |     |              |              |       | KA                             |              | mm²        | mm²    | CABLE (Mtrs) | mm²      | kW                  | kW      | kW      | kW    | (1)       | (2)  | (3)      |                   |
|     | INCOMER                       | TP  |              | 200<br>(N/A) |       | 30                             | FIRE PROOF   |            | 4C 95  |              | 1C 50    |                     |         |         |       |           |      |          |                   |
|     | OUTGOING                      |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
| 1   | DB-UPS                        | TP  |              | 40           |       | 30                             | XLPE/SWA/PVC |            | 4C 10  |              | 1C 10    | 5.60                | 6.80    | 4.80    | 17.20 |           |      |          | 40KVA UPS         |
| 2   | DB-MTR                        | TP  |              | 40           |       | 30                             | XLPE/SWA/PVC |            | 4C 10  |              | 1C 10    | 2.20                | 2.30    | 1.40    | 5.90  |           |      |          | *                 |
| 3   | CBS PANEL                     | TP  |              | 20           |       | 30                             | FIRE PROOF   |            | 4C 4   |              | 1C 4     | 1.00                | 1.00    | 1.00    | 3.00  |           |      |          | *                 |
| 4   | DX-2                          | TP  |              | 40           |       | 30                             | XLPE/SWA/PVC |            | 4C 10  |              | 1C 10    | 5.67                | 5.67    | 5.67    | 17.00 |           |      |          | *                 |
| 5   | CCU-1                         | TP  |              | 63           |       | 30                             | XLPE/SWA/PVC |            | 4C 16  |              | 1C 16    | 7.50                | 7.50    | 7.50    | 22.50 |           |      |          | UVR+TIMER+CONTACT |
| 6   | CCU-2                         | TP  |              | 63           |       | 30                             | XLPE/SWA/PVC |            | 4C 16  |              | 1C 16    | 7.50                | 7.50    | 7.50    | 22.50 |           |      |          | UVR+TIMER+CONTACT |
|     |                               |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
|     |                               |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
|     |                               |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
|     |                               |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
|     |                               |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
|     |                               |     |              |              |       |                                |              |            |        |              |          |                     |         |         |       |           |      |          |                   |
| 5   | SMDB - BE3 CONNECTED TO MDB-E |     |              |              |       | TOTAL CONNECTED LOAD PER PHASE |              |            |        |              |          | 29.47               | 30.77   | 27.87   | 88.10 |           |      |          | TOTAL             |

DEMAND FACTOR...... MAX. DEMAND.......kW TOTAL CONNECTED LOAD (3 PHASE)...88.10...kW TOTAL BUILD - UP AREA ....... ACTUAL LOAD (3 PH).....kW

CONSULTANTS : **M/S. IAN BANHAM AND ASSOCIATES**TEL : 04 - 370 5777

FAX : 04 - 370 5888