PROJECT : B+G+M+1 FLOOR CAR SHOWROOM & OFFICE BUILDING DETAILS OF CONNECTED LOAD/MAX. DEMAND

SMDB REF : SMDB - IN1 CONSULTANT : M/S. IAN BANHAM & ASSOCIATES LOCATION : ELECT ROOM

1ST FLOOR

SR.	CIRCUIT	SP/	RATING - AMPS		/PS	FAULT	F PVC/XLPE	CABLE SIZE		LENGTH	ECC	CONNECTED LOAD - KW				KWH METER			REMARKS
NO		FEEDER TP ACB MCCB MC				SWA/PVC/SC			OF	SIZE -1C			<u> </u>		1 Ph 3 Ph LV/HV CT			. CLIVII II II II	
NO	DB NO.	''	1 105	MOOD	WOD	KA	011711 10700	mm²	mm <sup>2</sup>	CABLE (Mtrs)	mm²	kW	kW	kW	kW	(1)		(3)	
	INCOMER	TP		400		30	XLPE/SWA/PVC	111111	4C 300	CABLE (Mtrs)	1C 150			I I		(1)	(2)	(3)	
	OUTGOING			(N/A)															
1	DB-1N1	TP		100		30	XLPE/SWA/PVC		4C 35		1C 16	17.60	13.30	16.60	47.50				*
2	CAR LIFT	TP		125		30	XLPE/SWA/PVC		4C 50		1C 25	18.33	18.33	18.33	55.00				*
3	CAR LIFT	TP		125		30	XLPE/SWA/PVC		4C 50		1C 25	18.33	18.33	18.33	55.00				*
4	CAR LIFT CONTROL	SP		20		30	XLPE/SWA/PVC		2C 4		1C 4	0.50			0.50				*
4	CAR LIFT CONTROL	SP		20		30	XLPE/SWA/PVC		2C 4		1C 4		0.50		0.50				*
4	SPARE	SP		80		30													
5	EV CHARGER	TP		63		30	XLPE/SWA/PVC		4C 16		1C 16	7.33	7.33	7.33	22.00				*
		_																	
		-																	
	 SMDB - IN1 CONNECT	ED TO	<u> </u>	V MDB-	1														
						TOTAL CONNECTED LOAD PER PHASE						62.10	57.80	60.60	180.50				TOTAL

DEMAND FACTOR..... MAX. DEMAND.......kW TOTAL CONNECTED LOAD (3 PHASE)...180.50...kW TOTAL BUILD - UP AREA ....... ACTUAL LOAD (3 PH).....kW

CONSULTANTS : **M/S. IAN BANHAM AND ASSOCIATES**TEL : 04 - 370 5777

FAX : 04 - 370 5888

(1 PHASE) (3 PHASE)